

12mm	1	4	1.00	4.00	0.89	3.56			
ring 8mm	1	7	0.60	4.20	0.39	1.64			
12mm	1	4	1.40	5.60	0.89	4.98			
ring 8mm	1	10	0.60	6.00	0.39	2.34			
QTY FOR ABOVE 125%					TOTAL	6916.90	Kgs		
SR 2015-16	54900.00				TOTAL	6.91	MT		
AW 6 %	3294.00				BOQ QTY	4.83		65188.00	314858.04
TOTAL	58194.00				UP TO 125% QTY	1.20		65188.00	78225.60
ADD TP 11.95%	7004.18				ABOVE 125% QTY	0.88		65187.63	57365.11
GRAND TOTAL	65187.63								
Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500. First Floor									
FF for column for GF roof to FF roof C1 25mm	2	8	3.50	56.00	3.86	216.16			
ring 8mm	2	20	1.30	52.00	0.39	20.28			
ring 8mm	2	20	0.80	32.00	0.39	12.48			
C2 25mm	3	4	3.50	42.00	3.86	162.12			
20mm	3	4	3.50	42.00	2.48	104.16			
ring 8mm	3	20	1.30	78.00	0.39	30.42			
ring 8mm	3	20	0.80	48.00	0.39	18.72			
C3 20mm*	5	8	3.50	140.00	2.48	347.20			
ring 8mm	5	20	1.30	130.00	0.39	50.70			
ring 8mm	5	20	0.50	50.00	0.39	19.50			
C4 20mm	2	4	3.50	28.00	2.48	69.44			
16mm	2	4	3.50	28.00	1.58	44.24			
ring 8mm	2	20	1.30	52.00	0.39	20.28			
ring 8mm	2	20	0.80	32.00	0.39	12.48			
level difference C3 20mm	3	8	1.05	25.20	2.48	62.50			
ring 8mm	3	7	1.30	27.30	0.39	10.65			
ring 8mm	3	7	0.80	16.80	0.39	6.55			
C2 25mm	2	4	1.05	8.40	3.86	32.42			
20mm	2	4	1.05	8.40	2.48	20.83			
ring 8mm	2	7	1.30	18.20	0.39	7.10			
roor beam B3 25mm top&bottom	1	4	7.40	29.60	3.86	114.26			
extra rod at top 25mm	1	2	2.40	4.80	3.86	18.53			
at bottom 25mm	1	2	4.80	9.60	3.86	37.06			
at top 25mm	1	2	2.40	4.80	3.86	18.53			
ring 8mm	1	42	1.60	67.20	0.62	41.66			
B2 16mm top&bottom	2	4	7.40	59.20	1.58	93.54			
extra rod at top 16mm	2	2	1.70	6.80	1.58	10.74			
at bottom 16mm	2	2	2.25	9.00	1.58	14.22			
at top 20mm	2	2	2.30	9.20	2.48	22.82			
at bottom 16mm	2	2	2.25	9.00	1.58	14.22			
at top 20mm	2	2	1.62	6.48	2.18	14.13			
ring 8mm	2	42	1.30	109.20	0.62	67.70			
B4 16mm top&bottom	1	4	10.00	40.00	1.58	63.20			
extra rod at top 16mm	1	2	1.50	3.00	1.58	4.74			

at bottom 16mm	1	2	2.35	4.70	1.58	7.43			
at top 20mm	1	2	7.70	15.40	2.48	38.19			
ring 8mm	1	55	1.30	71.50	0.39	27.89			
B5 20mm top&bottom	1	4	10.00	40.00	2.48	99.20			
extra rod at top 20mm	1	2	2.55	5.10	2.48	12.65			
at bottom 16mm	1	2	4.35	8.70	1.58	13.75			
at top 20mm	1	2	5.15	10.30	2.48	25.54			
ring 8mm	1	55	1.30	71.50	0.39	27.89			
B2 16mm top&bottom	1	4	10.80	43.20	1.58	68.26			
extra rod at top 20mm	1	2	1.85	3.70	2.48	9.18			
at bottom 16mm	1	2	2.40	4.80	1.58	7.58			
at top 20mm	1	2	2.30	4.60	2.48	11.41			
at bottom 16mm	1	2	2.40	4.80	1.58	7.58			
at top 20mm	1	2	2.30	4.60	2.48	11.41			
at bottom 16mm	1	2	2.40	4.80	1.58	7.58			
at top 20mm	1	2	1.65	3.30	2.48	8.18			
ring 8mm	1	60	1.30	78.00	0.39	30.42			
B2 a 16mm top&bottom	1	2	10.80	21.60	1.58	34.13			
extra rod at top 20mm	1	2	1.50	3.00	2.48	7.44			
at bottom 16mm	1	2	2.30	4.60	1.58	7.27			
at top 20mm	1	2	2.45	4.90	2.48	12.15			
at bottom 16mm	1	2	2.30	4.60	1.58	7.27			
at top 20mm	1	2	2.20	4.40	2.48	10.91			
at bottom 16mm	1	2	2.30	4.60	1.58	7.27			
ring 10mm	1	60	1.30	78.00	0.62	48.36			
B6 16mm top&bottom	1	6	5.90	35.40	1.58	55.93			
ring 8mm	1	32	1.30	41.60	0.39	16.22			
B7 16mm top&bottom	1	6	2.40	14.40	1.58	22.75			
ring 8mm	1	11	1.30	14.30	0.39	5.58			
16mm	1	6	4.30	25.80	1.58	40.76			
ring 8mm	1	20	1.60	32.00	0.39	12.48			
16mm	1	6	3.40	20.40	1.58	32.23			
ring 8mm	1	16	1.30	20.80	0.39	8.11			
16mm	1	6	4.80	28.80	1.58	45.50			
ring 8mm	1	25	1.30	32.50	0.39	12.68			
for roof main rod 10mm	1	69	6.85	472.65	0.62	293.04			
extra rod 10mm	2	35	2.30	161.00	0.62	99.82			
	1	35	2.10	73.50	0.62	45.57			
dist 10mm	1	55	6.90	379.50	0.62	235.29			
extra rod 10mm	2	28	2.15	120.40	0.62	74.65			
passage roof main rod 10mm	1	43	2.60	111.80	0.62	69.32			
dist 10mm	1	21	5.30	111.30	0.62	69.01			
extra rod 10mm	2	23	1.00	46.00	0.62	28.52			
main rod 10mm	1	19	1.50	28.50	0.62	17.67			
dist 10mm	1	12	1.90	22.80	0.62	14.14			
for stair case 12mm	1	16	8.70	139.20	0.89	123.89			
extra rod at bottom 12mm	1	16	2.40	38.40	0.89	34.18			
extra rod at top 12mm	1	16	3.20	51.20	0.89	45.57			

dist 12mm	1	40	1.50	60.00	0.89	53.40			
	2	10	1.50	30.00	0.89	26.70			
for landing 12mm	2	14	3.45	96.60	0.89	85.97			
2nd flight 12mm	1	16	6.40	102.40	0.89	91.14			
extra rod at bottom 12mm	1	16	2.70	43.20	0.89	38.45			
at top 12mm	1	16	3.60	57.60	0.89	51.26			
dist 12mm	1	12	1.50	18.00	0.89	16.02			
for lintel beam 16mm	1	4	3.20	12.80	1.58	20.22			
8mm	1	22	0.80	17.60	0.39	6.86			
12mm	1	4	6.80	27.20	0.89	24.21			
8mm	1	45	0.60	27.00	0.39	10.53			
12mm	1	4	1.00	4.00	0.89	3.56			
8mm	1	7	0.60	4.20	0.39	1.64			
12mm	1	4.00	1.40	5.60	0.89	4.98			
8mm	1	10.00	0.60	6.00	0.39	2.34			
for chajja main rod 10mm	1	18.00	0.85	15.30	0.62	9.49			
10mm	1	4.00	2.00	8.00	0.62	4.96			
QTY FOR ABOVE 125%					TOTAL	4207.13	Kgs		
SR 2015-16 54900.00					TOTAL	4.20	MT		
LIFT CHARGES FOR 1ST FLOOR 400.00					BOQ QTY	2.53		65716.00	166261.48
AW 6 % 3318.00					UP TO 125% QTY	0.63		65716.00	41401.08
TOTAL - 58618.00					ABOVE 125% QTY	1.04		65716.71	68345.38
ADD TP 11.95% 6562.71									
GRAND TOTAL 65716.71									
Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500. Second Floor									
or column from FF to SF roof C1 25mm	2	8	4.50	72.00	3.86	277.92			
ring 8mm	2	20	1.30	52.00	0.39	20.28			
ring 8mm	2	20	0.80	32.00	0.39	12.48			
C2 25mm	3	4	4.50	54.00	3.86	208.44			
20mm	3	4	4.50	54.00	2.48	133.92			
ring 8mm	3	20	1.30	78.00	0.39	30.42			
ring 8mm	3	20	0.80	48.00	0.39	18.72			
C3 20mm	5	8	4.50	180.00	2.48	446.40			
ring 8mm	5	20	1.30	130.00	0.39	50.70			
ring 8mm	5	20	0.50	50.00	0.39	19.50			
C4 20mm	2	4	3.50	28.00	2.48	69.44			
16mm	2	4	3.50	28.00	1.58	44.24			
ring 8mm	2	20	1.30	52.00	0.39	20.28			
ring 8mm	2	20	0.80	32.00	0.39	12.48			
level difference C3 20mm	3	8	1.05	25.20	2.48	62.50			
ring 8mm	3	7	1.30	27.30	0.39	10.65			
ring 8mm	3	7	0.80	16.80	0.39	6.55			
C2 25mm	2	4	1.05	8.40	3.86	32.42			
20mm	2	4	1.05	8.40	2.48	20.83			
ring 8mm	2	7	1.30	18.20	0.39	7.10			

head room 20mm	4	8	3.25	104.00	2.48	257.92			
ring 8mm	4	20	1.30	104.00	0.39	40.56			
ring 8mm	4	20	0.80	64.00	0.39	24.96			
20mm	2	8	1.80	28.80	2.48	71.42			
ring 8mm	2	12	1.30	31.20	0.39	12.17			
ring 8mm	2	12	0.80	19.20	0.39	7.49			
roor beam B3 25mm top&bottom	1	4	7.40	29.60	3.86	114.26			
extra rod at top 25mm	1	2	2.40	4.80	3.86	18.53			
at bottom 25mm	1	2	4.80	9.60	3.86	37.06			
at top 25mm	1	2	2.40	4.80	3.86	18.53			
ring 8mm	1	42	1.60	67.20	0.39	26.21			
B2 16mm top&bottom	2	4	7.40	59.20	1.58	93.54			
extra rod at top 16mm	2	2	1.70	6.80	1.58	10.74			
at bottom 16mm	2	2	2.25	9.00	1.58	14.22			
at top 20mm	2	2	2.30	9.20	2.48	22.82			
at bottom 16mm	2	2	2.25	9.00	1.58	14.22			
at top 20mm	2	2	1.62	6.48	2.18	14.13			
ring 8mm	2	42	1.30	109.20	0.39	42.59			
B4 16mm top&bottom	1	4	10.00	40.00	1.58	63.20			
extra rod at top 16mm	1	2	1.50	3.00	1.58	4.74			
at bottom 16mm	1	2	2.35	4.70	1.58	7.43			
at top 20mm	1	2	7.70	15.40	2.48	38.19			
ring 8mm	1	55	1.30	71.50	0.39	27.89			
B5 20mm top&bottom	1	4	10.00	40.00	2.48	99.20			
extra rod at top 20mm	1	2	2.55	5.10	2.48	12.65			
at bottom 16mm	1	2	4.35	8.70	1.58	13.75			
at top 20mm	1	2	5.15	10.30	2.48	25.54			
ring 8mm	1	55	1.30	71.50	0.39	27.89			
B2 16mm top&bottom	1	4	10.80	43.20	1.58	68.26			
extra rod at top 20mm	1	2	1.85	3.70	2.48	9.18			
at bottom 16mm	1	2	2.40	4.80	1.58	7.58			
at top 20mm	1	2	2.30	4.60	2.48	11.41			
at bottom 16mm	1	2	2.40	4.80	1.58	7.58			
at top 20mm	1	2	2.30	4.60	2.48	11.41			
at bottom 16mm	1	2	2.40	4.80	1.58	7.58			
at top 20mm	1	2	1.65	3.30	2.48	8.18			
ring 8mm	1	60	1.30	78.00	0.39	30.42			
B2 a 16mm top&bottom	1	2	10.80	21.60	1.58	34.13			
extra rod at top 20mm	1	2	1.50	3.00	2.48	7.44			
at bottom 16mm	1	2	2.30	4.60	1.58	7.27			
at top 20mm	1	2	2.45	4.90	2.48	12.15			
at bottom 16mm	1	2	2.30	4.60	1.58	7.27			
at top 20mm	1	2	2.20	4.40	2.48	10.91			
at bottom 16mm	1	2	2.30	4.60	1.58	7.27			
ring 8mm	1	60	1.30	78.00	0.39	30.42			
B6 16mm top&bottom	1	6	5.90	35.40	1.58	55.93			
ring 10mm	1	32	1.30	41.60	0.39	16.22			
B7 16mm top&bottom	1	6	2.40	14.40	1.58	22.75			

ring 8mm	1	11	1.30	14.30	0.39	5.58			
16mm	1	6	4.30	25.80	1.58	40.76			
ring 8mm	1	20	1.60	32.00	0.39	12.48			
16mm	1	6	3.40	20.40	1.58	32.23			
ring 8mm	1	16	1.30	20.80	0.39	8.11			
16mm	1	6	4.80	28.80	1.58	45.50			
ring 8mm	1	25	1.30	32.50	0.39	12.68			
for roof main rod 10mm	1	69	6.85	472.65	0.62	293.04			
extra rod 10mm	2	35	2.30	161.00	0.62	99.82			
	1	35	2.10	73.50	0.62	45.57			
dist 10mm	1	55	6.90	379.50	0.62	235.29			
extra rod 10mm	2	28	2.15	120.40	0.62	74.65			
passage roof main rod 10mm	1	43	2.60	111.80	0.62	69.32			
dist 10mm	1	21	5.30	111.30	0.62	69.01			
extra rod 10mm	2	23	1.00	46.00	0.62	28.52			
main rod 10mm	1	19	1.50	28.50	0.62	17.67			
dist 10mm	1	12	1.90	22.80	0.62	14.14			
head room 10mm	1	69	3.55	244.95	0.62	151.87			
10mm	1	28	6.80	190.40	0.62	118.05			
extra rod 10mm	2	35	1.20	84.00	0.62	52.08			
	2	14	1.00	28.00	0.62	17.36			
for stair case 12mm	1	16	8.70	139.20	0.89	123.89			
extra rod at bottom 12mm	1	16	2.40	38.40	0.89	34.18			
extra rod at top 12mm	1	16	3.20	51.20	0.89	45.57			
dist 12mm	1	40	1.50	60.00	0.89	53.40			
	2	10	1.50	30.00	0.89	26.70			
for landing 12mm	2	14	3.45	96.60	0.89	85.97			
2nd flight 12mm	1	16	6.40	102.40	0.89	91.14			
extra rod at bottom 12mm	1	16	2.70	43.20	0.89	38.45			
at top 12mm	1	16	3.60	57.60	0.89	51.26			
dist 12mm	1	12	1.50	18.00	0.89	16.02			
for lintel beam 12mm	1	4	1.40	5.60	0.89	4.98			
ring 8mm	1	10	0.60	6.00	0.39	2.34			
12mm	1	4.00	3.35	13.40	0.89	11.93			
ring 8mm	1	23.00	0.60	13.80	0.39	5.38			
12mm	1	4.00	1.00	4.00	0.89	3.56			
8mm	1	7.00	0.60	4.20	0.39	1.64			
for chajja main rod 10mm	1	18.00	0.85	15.30	0.62	9.49			
10mm	1	4.00	2.00	8.00	0.62	4.96			
QTY FOR ABOVE 125%					TOTAL	5095.02	Kgs		
SR 2015-16	54900.00				TOTAL	5.09	MT		
LIFT CHARGES FOR 2ND FLOOR	800.00				BOQ QTY	2.64		66244.00	174884.16
AW 6 %	3342.00				UP TO 125% QTY	0.66		66244.00	43721.04
TOTAL	59042.00				ABOVE 125% QTY	1.79		66243.78	118576.37
ADD TP 11.95%	7255.78								
GRAND TOTAL	66243.78								

Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. <u>Ground Floor</u>									
		1	2.60		2.30	5.98	✓		
deductions		-1	0.45		2.30	-1.04	✓		
		1	6.62		2.30	15.23	✓		
deductions column		-1	0.45		2.30	-1.04	✓		
v		-1	1.20		0.60	-0.72	✓		
		1	6.80		2.30	15.64	✓		
deductions column		-3	0.45		2.30	-3.11	✓		
v		-2	1.20		0.60	-1.44	✓		
v		-1	0.60		0.60	-0.36	✓		
		1	10.23		2.30	23.53	✓		
deductions column		-3	0.45		2.30	-3.11	✓		
v		-1	0.75		0.60	-0.45	✓		
		-2	0.60		0.60	-0.72	✓		
		-1	1.20		0.60	-0.72	✓		
w		-1	1.80		1.50	-2.70	✓		
		1	6.80		2.30	15.64	✓		
		1	2.80		0.65	1.82	✓		
		1	1.80		3.35	6.03	✓		
		1	6.80		2.30	15.64	✓		
		1	1.60		0.65	1.04	✓		
deductions		-1	1.50		2.50	-3.75	✓		
QTY FOR ABOVE 125%				TOTAL		81.41	✓ Sqm		
SR 2015-16	943.00			BOQ QTY		52.38	✓	1119.00	58613.22
AW 6 %	56.58			UP TO 125% QTY		13.09	✓	1119.00	14647.71
TOTAL	999.58			ABOVE 125% QTY		15.94	✓	1119.02	17831.58
ADD TP 11.95%	119.44								
GRAND TOTAL	1119.02								
Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. <u>First Floor</u>									
		1	2.60		3.05	7.93	✓		
		1	6.62		3.05	20.19	✓		
		1	6.80		3.05	20.74	✓		
		1	10.23		3.05	31.20	✓		
		1	6.80		3.05	20.74	✓		
		1	2.80		3.05	8.54	✓		
		1	5.30		3.35	17.76	✓		
		1	1.80		3.35	6.03	✓		
		1	6.80		3.05	20.74	✓		
		1	1.60		0.65	1.04	✓		
deductions column		-8	0.45		3.05	-10.98	✓		
v		-4	1.20		0.60	-2.88	✓		
		-3	0.60		0.60	-1.08	✓		
v1		-1	0.75		0.60	-0.45	✓		

w		-1	1.80		1.50	-2.70	✓		
open		-1	1.50		2.50	-3.75	✓		
QTY FOR ABOVE 125%					TOTAL	133.07	✓ Sqm		
SR 2015-16	943.00				BOQ QTY	85.54	✓	1155.00	98798.70
LIFT CHARGES FOR 1ST FLOOR	30.00				UP TO 125% QTY	21.38	✓	1155.00	24693.90
AW 6 %	58.38				ABOVE 125% QTY	26.15	✓	1154.52	30187.81
TOTAL	1031.38								
ADD TP 11.95%	123.24								
GRAND TOTAL	1154.52								
Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Second Floor									
entrance		1	2.60		3.05	7.93	✓		
outer wall west side		1	6.62		3.05	20.19	✓		
outer wall south side		1	6.80		3.05	20.74	✓		
outer wall east side		1	10.23		3.05	31.20	✓		
entrance		1	6.80		3.05	20.74	✓		
entrance		1	2.80		3.05	8.54	✓		
		1	5.30		3.35	17.76	✓		
		1	1.80		3.35	6.03	✓		
stair case		1	6.80		3.05	20.74	✓		
		1	1.60		0.65	1.04	✓		
deductions column		-8	0.45		3.05	-10.98	✓		
v		-4	1.20		0.60	-2.88	✓		
		-3	0.60		0.60	-1.08	✓		
v1		-1	0.75		0.60	-0.45	✓		
w		-1	1.80		1.50	-2.70	✓		
open		-1	1.50		2.50	-3.75	✓		
head room		1	6.8		3.25	22.10	✓		
		1	3.55		3.25	11.54	✓		
		1	2.75		1.8	4.95	✓		
deductions		-4	0.45		3.25	-5.85	✓		
		-1	0.20		3.25	-0.65	✓		
2nd bill for parpet wall		1	29.70		1.00	29.70	✓		
QTY FOR ABOVE 125%					TOTAL	194.86	✓ Sqm		
SR 2015-16	943.00				BOQ QTY	85.54	✓	1190.00	101792.60
LIFT CHARGES FOR 2ND FLOOR	60.00				UP TO 125% QTY	21.38	✓	1190.00	25442.20
AW 6 %	60.18				ABOVE 125% QTY	87.94	✓	1190.23	104662.88
TOTAL	1063.18								
ADD TP 11.95%	127.05								
GRAND TOTAL	1190.23								
Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Ground Floor									
store		1	2.10		2.30	4.83	✓		
deductions		-1	0.75		2.10	-1.58	✓		
		1	3.35		2.30	7.71	✓		

toilets		1	3.35		2.30	7.71	✓		
		3	1.20		2.30	8.28	✓		
entrance		1	1.90		2.30	4.37	✓		
		1	1.30		2.30	2.99	✓		
		1	1.20		2.30	2.76	✓		
deductions D1		-3	0.75		2.10	-4.73	✓		
D2		-1	1.20		2.10	-2.52	✓		
					TOTAL	29.82	✓ Sqm		
					BOQ QTY	26.33	✓	816.00	21485.28
					UP TO 125% QTY	3.59	✓	816.00	2929.44
152 Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. First Floor									
Toilet		1	6.40		3.35	21.44	✓		
partions		5	1.20		3.35	20.10	✓		
store		1	2.40		3.35	8.04	✓		
		1	2.45		3.35	8.21	✓		
near entrance		1	2.15		3.35	7.20	✓		
		1	1.20		3.35	4.02	✓		
deductions		-7	0.75		2.10	-11.03	✓		
		-1	1.20		2.10	-2.52	✓		
					TOTAL	55.47	✓ Sqm		
					BOQ QTY	48.81	✓	852.00	41586.12
					UP TO 125% QTY	6.66	✓	852.00	5674.32
153 Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Second Floor									
store		1	2.10		3.35	7.04	✓		
		1	3.35		3.35	11.22	✓		
toilet		1	3.35		3.35	11.22	✓		
		3	1.20		3.35	12.06	✓		
		1	1.90		3.35	6.37	✓		
		1	1.30		3.35	4.36	✓		
		1	1.20		3.35	4.02	✓		
deductions		-4	0.75		2.10	-6.30	✓		
		-1	1.20		2.10	-2.52	✓		
					TOTAL	47.46	✓ Sqm	888.00	42144.48
154 Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification									
GF 1st flight		1	6.10	1.80		10.98			
2nd flight		1	2.10	1.80		3.78			
landing		1	3.45	1.50		5.18			
		1	1.20	1.50		1.80			
		1	6.45	6.45		41.60			

FF 1st flight		1	5.50	1.80		9.90			
2nd flight		1	2.75	1.80		4.95			
landing		1	3.25	1.55		5.04			
		1	1.15	1.50		1.73			
		1	6.45	6.45		41.60			
SF 1st flight		1	5.50	1.80		9.90			
2nd flight		1	2.75	1.80		4.95			
landing		1	3.25	1.55		5.04			
		1	1.15	1.50		1.73			
		1	6.45	6.45		41.60			
head room		1	3.15	3.25		10.24			
QTY FOR ABOVE 125%					TOTAL	200.01	Sqm		
SR 2015-16	207.00				BOQ QTY	126.75		246.00	31180.50
AW 6 %	12.42				UP TO 125% QTY	31.68		246.00	7793.28
TOTAL	219.42				ABOVE 125% QTY	41.58		245.64	10212.48
ADD TP 11.95%	26.22								
GRAND TOTAL	245.64								
Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge for Inside Ground Floor									
near steps		2	9.10		2.75	50.05			
		2	3.00		2.75	16.50			
entrance		1	2(1.40+3.10)		2.75	24.75			
		1	1.90		2.75	5.23			
		1	3.10		2.75	8.53			
		1	3.30		2.75	9.08			
		1	1.40		2.75	3.85			
		1	4.90		2.75	13.48			
		1	1.70		2.75	4.68			
		1	2(2.10+1.50)		2.75	19.80			
		2	3.35		2.75	18.43			
		1	3.00		2.75	8.25			
toilets		3	2(2.10+1.50)		2.75	59.40			
deductions		-0.5	2.15		2.30	-2.47			
		-0.5	1.55		2.30	-1.78			
		-0.5	1.45		2.10	-1.52			
D1	-0.5	4	0.75		2.1	-3.15			
v	-0.5	4	1.20		0.60	-1.44			
v1	-0.5	3	0.60		0.60	-0.54			
v2	-0.5	1	0.75		0.60	-0.22			
w	-0.5	1	1.80		1.50	-1.35			
QTY FOR ABOVE 125%					TOTAL	229.52	Sqm		
SR 2015-16	234.00				BOQ QTY	114.14		278.00	31730.92
AW 6 %	14.04				UP TO 125% QTY	28.53		278.00	7931.34
TOTAL	248.04				ABOVE 125% QTY	86.85		277.68	24117.20
ADD TP 11.95%	29.64								
GRAND TOTAL	277.68								

Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge for Inside First Floor

near steps		2	9.10		3.45	62.79			
		2	3.00		3.45	20.70			
near entrance		1	4.80		3.45	16.56			
		2	2.15		3.45	14.84			
		1	2.40		3.45	8.28			
store		1	2(1.50+2.40)		3.45	26.91			
		1	2.45		3.45	8.45			
		1	0.85		3.45	2.93			
		1	6.40		3.45	22.08			
toilets	1	6	2(1.10+1.20)		3.45	95.22			
deductions	1	-0.5	1.20		0.60	-0.36			
	-0.5	7	0.60		0.60	-1.26			
D1	-0.5	7	0.75		2.10	-5.51			
D	-0.5	1	1.20		2.10	-1.26			
QTY FOR ABOVE 125%					TOTAL	270.37	Sqm		
SR 2015-16	234.00				BOQ QTY	200.40		284.00	56913.60
LIFT CHARGES FOR 1ST FLOOR	5.00				UP TO 125% QTY	50.10		284.00	14228.40
AW 6 %	14.34				ABOVE 125% QTY	19.87		283.61	5635.33
TOTAL	253.34								
ADD TP 11.95%	30.27								
GRAND TOTAL	283.61								

Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge for Inside Second Floor

near steps		2	9.10		3.45	62.79			
		2	3.00		3.45	20.70			
entrance		1	2(1.40+3.10)		3.45	31.05			
	1	1	1.90		3.45	6.56			
	1	1	3.10		3.45	10.70			
	1	1	3.30		3.45	11.39			
	1	1	1.40		3.45	4.83			
	1	1	4.90		3.45	16.91			
	1	1	1.70		3.45	5.87			
store		1	2(2.10+1.50)		3.45	24.84			
	1	2	3.35		3.45	23.12			
	1	1	3.00		3.45	10.35			
toilets		3	2(1.20+1.00)		3.45	45.54			
deductions		-0.5	2.15		3.05	-3.28			
	1	-0.5	1.55		3.05	-2.36			
	1	-0.5	1.45		2.10	-1.52			
D	4	-0.5	0.75		2.10	-3.16			
V	4	-0.5	1.20		0.60	-1.44			
V2	1	-0.5	0.75		0.60	-0.23			
V1	3	-0.5	0.60		0.60	-0.54			

W	1	-0.5	1.80		1.50	-1.35			
QTY FOR ABOVE 125%					TOTAL	260.74	Sqm		
SR 2015-16	234.00				BOQ QTY	200.40		290.00	58116.00
LIFT CHARGES FOR 2ND FLOOR	10.00				UP TO 125% QTY	50.10		290.00	14529.00
AW 6 %	14.64				ABOVE 125% QTY	10.24		289.54	2964.89
TOTAL	258.64								
ADD TP 11.95%	30.90								
GRAND TOTAL	289.54								
Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. Ground Floor									
Ground Floor west side		1	2.60	2.70		7.02			
		1	6.62	2.70		17.87			
south side		1	6.80	2.70		18.36			
east side		1	7.15	2.70		19.31			
		1	3.10	2.70		8.37			
north side		1	7.70	2.70		20.79			
QTY FOR ABOVE 125%					TOTAL	91.72	Sqm		
SR 2015-16	210.00				BOQ QTY	59.64		249.00	14850.36
AW 6 %	12.60				UP TO 125% QTY	14.91		249.00	3712.59
TOTAL	222.60				ABOVE 125% QTY	17.17		249.20	4278.51
ADD TP 11.95%	26.60								
GRAND TOTAL	249.20								
Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. First Floor									
First floor west side		1	5.30	3.50		18.55			
		1	2.60	3.50		9.10			
		1	6.62	3.50		23.17			
south side		1	6.80	3.50		23.80			
east side		1	7.15	3.50		25.03			
		1	3.10	3.50		10.85			
north side		1	7.70	3.50		26.95			
QTY FOR ABOVE 125%		1	1.80	3.50		6.30			
SR 2015-16	210.00				TOTAL	143.75	Sqm		
LIFT CHARGES FOR 2ND FLOOR	10.00				BOQ QTY	99.58		261.00	25990.38
AW 6 %	13.20				UP TO 125% QTY	24.89		261.00	6496.29
TOTAL	233.20				ABOVE 125% QTY	19.28		261.06	5031.93
ADD TP 11.95%	27.86								
GRAND TOTAL	261.06								
Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. Second Floor									
second floor west side		1	5.30	6.50		34.45			
		1	2.60	6.85		17.81			
		1	6.62	6.30		41.71			

south side		1	6.80	6.30		42.84			
east side		1	7.13	8.30		59.18			
		1	3.10	8.30		25.73			
north side		1	7.70	8.30		63.91			
QTY FOR ABOVE 125%		1	1.80	6.50		11.70			
SR 2015-16	210.00				TOTAL	297.33	Sqm		
LIFT CHARGES FOR 2ND FLOOR	20.00				BOQ QTY	99.58		273.00	27185.34
AW 6 %	13.80				UP TO 125% QTY	24.89		273.00	6794.97
TOTAL	243.80				ABOVE 125% QTY	172.86		272.93	47177.32
ADD TP 11.95%	29.13								
GRAND TOTAL	272.93								
Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size of 30x30cms 6mm thick. Ground Floor									
2nd floor ground floor toilet		1	3	1.20	1.00	3.60			
		1	1	2.80	3.40	9.52			
west side area		1	1	4.30	1.75	7.53			
		1	1	1.35	1.40	1.89			
		1	1	1.30	3.15	4.10			
		1	1	3.40	2.05	6.97			
store			1	1.50	2.10	3.15			
					TOTAL	36.75	Sqm	1334.00	49024.50
Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size of 30x30cms 6mm thick. First Floor									
2nd floor First floor toilet		1	6	1.20	0.90	6.48			
west side			1	2.55	2.53	6.45			
			1	1.15	0.60	0.69			
			1	2.15	3.75	8.06			
			1	4.15	2.55	10.58			
store			1	2.38	1.45	3.45			
					TOTAL	35.72	Sqm	1336.00	47718.58
Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size of 30x30cms 6mm thick. Second Floor									
2nd floor second floor toilet		1	3	0.95	1.15	3.28			
store		1	1	2.15	1.45	3.12			
west side		1	1	2.84	3.35	9.51			
		1	1	4.23	1.78	7.53			
		1	1	1.30	1.45	1.89			
		1	1	3.12	1.32	4.12			
		1	1	2.12	3.50	7.42			
					TOTAL	36.86	Sqm	1337.00	49284.23
Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. Ground Floor									
Ground floor toilet		1	3	2(1.20+1.00)	2.50	33.00			

Deductions V	1x0.5	-4	0.70	0.60		-0.84			
D	1x0.5	-3	0.75	2.10		-2.36			
West side		1	32.50	2.50		81.25			
Deductions w	1x0.5	-4	0.75	1.80		-2.70			
V	0.5	-3	1.20	0.60		-1.08			
D	0.5	-1	1.20	1.85		-1.11			
Store		1	2(1.50+2.10)	2.50		18.00			
deductions D	0.5	-1	0.75	1.85		-0.69			
V	0.5	-1	1.20	0.60		-0.36			
QTY FOR ABOVE 125%									
SR 2015-16	979.00				TOTAL	123.11	Sqm		
AW 6 %	58.74				BOQ QTY	65.02		1162.00	75553.24
TOTAL	1037.74				UP TO 125% QTY	16.25		1162.00	18882.50
ADD TP 11.95%	124.00				ABOVE 125% QTY	41.84		1161.74	48607.20
GRAND TOTAL	1161.74								
Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over roughj plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. First Floor									
First floor toilet	1	6	2(1.20+0.90)	2.10		26.46			
Deductions V	1x0.5	-6	0.75	1.85		-4.16			
West side		1	25.10	2.10		52.71			
Deductions w	0.5	-7	0.75	1.85		-4.85			
Store		1	2(1.45+2.38)	2.10		16.08			
deductions D	0.5	-1	0.75	1.85		-0.69			
					TOTAL	85.55	Sqm		
					BOQ QTY	70.73		1164.00	82329.72
					UP TO 125% QTY	14.82		1164.00	17250.48
Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over roughj plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. Second Floor									
Second floor toilet	1	3	2(0.95+1.15)	2.10		26.46			
Deductions	1x0.5	-4	0.70	0.60		-0.84			
	1x0.5	-3	0.75	1.85		-2.08			
West side		1	31.10	2.10		65.31			
Deductions	0.5	-4	0.75	1.80		-3.15			
Store		1	2(2.12+1.45)	2.10		14.99			
Deductions	0.5	-1	0.75	1.85		-0.69			
QTY FOR ABOVE 125%									
SR 2015-16	979.00				TOTAL	100.00	Sqm		
LIFT CHARGES FOR 2ND FLOOR	3.00				BOQ QTY	70.73		1165.00	82400.45
AW 6 %	58.92				UP TO 125% QTY	17.68		1165.00	20597.20
TOTAL	1040.92				ABOVE 125% QTY	11.59		1165.30	13505.83
ADD TP 11.95%	124.38								
GRAND TOTAL	1165.30								